





# MaxiForce Collapsible Bollard


Standard Body, Wrench Operated, Standard Style 1 Head, EZ Base

AHJ approved in many cities / counties / campuses for use in fire lanes per International Fire Code (IFC) 503




Patented fire hydrant wrench operation works with any standard fire hydrant wrench by turning the nut 1/4 turn to unlock and lower the bollard. (1-3/8" nut standard)  
*\*Free standard hydrant wrench included with each order*

Patented break-away design allows instant emergency access without a key. This unit can be pushed over with the bumper of a vehicle.




Shallow installation depth is great for use in parking decks, over shallow utilities or rocks, in foundations or anywhere minimal ground penetration is required.

- Low Maintenance / Durable steel construction
- One year warranty / Protected by \$1,000,000 in liability insurance
- No complex assembly required in the field
- Custom sizes, options, colors and finishes available upon request
- Finish options available (add code to the end of the model number)
  - Powder coated (PC)
  - Powder coated with DRYZINC primer (PCZ)
  - Hot dip galvanized (G)
  - Hot dip galvanized & powder coated (GPC)
- Reflective tape available upon request



Bollard Assy. Weight 58 lbs	Base Weight 5 lbs
Drawing Rev. 2	Created 11/27/2020
<b>PROPRIETARY AND CONFIDENTIAL</b>	
THIS DRAWING CONTAINS PROPRIETARY INFORMATION OF BLUE EMBER TECHNOLOGIES, LLC. ANY USE OF THIS DRAWING OR THE INFORMATION CONTAINED HEREIN FOR OTHER THAN THE PURPOSE FOR WHICH THIS DRAWING IS FURNISHED IS FORBIDDEN.	

**MaxiForce**  
7560 Main Street  
Sykesville, MD 21784  
tel: +1 (410) 552 9888  
sales@maxiforcebollards.com  
www.maxiforcebollards.com



**MCSW-SS1-EZ**

C

DO NOT SCALE DRAWING

SHEET 1 OF 1